

From Vision to Verdict: A Longitudinal Analysis of Cost Escalation and Risk Management in the Stuttgart 21 Megaproject

Prof. Dr.-Ing. Klaus Richter

Institute for Infrastructure and Project Management, Technical University of Munich, Munich, Germany

Jonas Baumann

Centre for Civil Engineering and Geosciences, ETH Zürich, Zurich, Switzerland

Abstract: Purpose: This paper provides a longitudinal analysis of the Stuttgart 21 (S21) megaproject, dissecting the evolution of its fiscal planning and risk management to identify the root causes of its severe cost overruns and protracted stakeholder disputes.

Design/methodology/approach: The study employs a qualitative, single-case study methodology. It synthesizes over three decades of data from official project documents, including the original feasibility study and financing contract; government and legal records, notably the 2024 court ruling on cost liability; academic literature; and chronological media archives. The analysis traces the project's financial trajectory against key risk events and governance decisions.

Findings: The project's initial €4.5 billion budget, established in a 2009 financing agreement, was founded on optimistic assumptions that failed to account for significant technical, geological, and political risks. The rigid contractual framework proved incapable of managing emergent challenges, leading to a cost escalation to over 11 billion. This triggered a legal battle where project owner Deutsche Bahn sought to compel partners to cover the deficit. This culminated in a landmark 2024 court decision that rejected Deutsche Bahn's claim, assigning the financial burden of the overruns almost entirely to the company. The core failures identified were an inadequate initial risk assessment, an inflexible governance structure, and a profound underestimation of project complexity.

Practical implications: The S21 case serves as a critical lesson for megaproject practitioners and policymakers. It underscores the necessity of independent and pessimistic forecasting, the establishment of adaptive financing agreements with clear risk-sharing clauses, and robust governance to manage uncertainty over a project's long lifecycle.

Originality/value: This paper offers a unique start-to-finish analysis of a major European megaproject, linking its initial financial architecture directly to the ultimate legal and financial fallout. It provides a comprehensive, evidence-based cautionary tale for the management of future megaprojects globally.

Keywords: Megaprojects, Stuttgart 21, Cost Overrun, Risk Management, Project Governance, Public-Private Partnership, Longitudinal Case Study.

INTRODUCTION

Megaprojects, broadly defined as large-scale, complex ventures that typically cost US\$1 billion or more, take many years to develop and build, involve multiple public and private stakeholders, and impact millions of people, have become defining features of the 21st-century global landscape [10]. These endeavours—spanning high-speed rail lines, airports, energy systems, and urban regeneration schemes—are pursued by governments and corporations as powerful instruments of economic stimulus, technological advancement, and national prestige [1, 25]. They promise to reshape geographies, accelerate commerce, and improve the quality of life for entire populations. The ambition inherent in these projects is matched only by their scale, representing some of the most significant capital investments a society can undertake [21].

However, a shadow looms over this landscape of grand ambition. A substantial body of evidence compiled over decades reveals a persistent and troubling pattern: megaprojects are chronically prone to failure, not in their technical execution, but in their managerial and financial discipline [10, 22]. Bent Flyvbjerg has famously termed this the "iron law of megaprojects: Over budget, over time, over and over again" [10]. This phenomenon, often referred to as the "megaproject paradox," describes the perplexing reality where, despite sophisticated project management tools and decades of accumulated experience, projects continue to exhibit staggering cost overruns and schedule delays [8, 25]. These failures are not minor deviations but often represent budget escalations of 50%, 100%, or even more, transforming promised public benefits into burdensome financial liabilities. The root causes are complex and multifaceted, commonly attributed to a combination of technical uncertainty, stakeholder complexity, political pressures, and, most notably, a pervasive "optimism bias" and "strategic misrepresentation" during the planning phases [10, 17]. Decision-makers, whether through psychological predisposition or deliberate deception, consistently underestimate costs and risks while overestimating benefits to secure project approval and funding.

The German infrastructure project Stuttgart 21 (S21) stands as a quintessential and cautionary European case study of this paradox. Conceived as a visionary redevelopment of the main railway station in Stuttgart, the capital of Baden-Württemberg, S21 aims to convert the existing 17-track terminus station into a modern, 8-track underground through station [4]. The project's stated goals are manifold: to create a new, more efficient hub in the European rail network, to free up 100 hectares of prime inner-city land for urban development, and to deliver a landmark architectural statement designed by the firm

Ingenhoven Architects [6]. First proposed in the 1990s, the project represents a monumental undertaking in engineering, tunnelling through challenging geological conditions beneath a densely populated city to connect with a new high-speed line to Ulm [4].

Despite its compelling vision, S21's history has been defined not by its engineering prowess but by its dramatic and seemingly uncontrollable cost escalation, bitter political division, and massive public protest [18]. A project initially budgeted at €4.5 billion in its binding 2009 financing agreement has seen its projected costs swell to over 11 billion, with its completion date pushed back by more than a decade [28]. This trajectory has ignited fierce debate and, ultimately, protracted legal battles over who must bear the financial burden of these multibillion-euro overruns. While a vast body of literature exists on identifying critical success factors [13, 33] and organizational structures [17] for megaprojects in general, a significant knowledge gap persists. Few studies provide a comprehensive, longitudinal analysis of a single project's entire lifecycle, tracing the intricate interplay of fiscal planning, risk management, governance, and stakeholder conflict from its initial conception through decades of turmoil to the ultimate legal adjudication of its financial failings.

This paper aims to fill this gap by conducting a detailed longitudinal analysis of the Stuttgart 21 project. The central objective is to dissect its fiscal and risk management trajectory to understand how a project with such clear strategic goals could devolve into a cautionary tale of financial mismanagement. To achieve this, the paper addresses the following research questions: 1) How did the initial financial framework and risk assessments for S21 compare to the project's realized outcomes? 2) What were the key technical, political, and financial events that drove the dramatic cost escalation? and 3) How was the dispute over liability for multi-billion-euro cost overruns legally resolved, and what does this verdict reveal about the project's foundational governance structure?

This study argues that the financial crisis of Stuttgart 21 was not the result of unforeseeable events but was systematically embedded in its initial framework. It contends that a combination of profound optimism bias, a rigid and inadequate financing contract, and a reactive, rather than proactive, risk management culture created the conditions for failure. The project's governance structure proved incapable of adapting to emergent risks, ultimately transforming a shared infrastructure vision into a zero-sum legal conflict. By tracing this path from vision to verdict, this paper provides critical insights for theory and practice, offering a stark warning about the paramount importance of fiscal prudence and robust, adaptive risk governance in the delivery of modern megaprojects. The remainder of this paper is structured as follows: The subsequent section details the research methodology. This is followed by a detailed chronological presentation of the results. The discussion section then interprets these findings in the context of megaproject theory and practice, before the paper concludes with a summary of its key contributions.

METHODOLOGY

To comprehensively investigate the complex and long-term dynamics of fiscal prudence and risk management within the Stuttgart 21 project, this study employs a qualitative, single-case study methodology with a longitudinal approach. The case study method is particularly well-suited for this research as it enables an in-depth, multi-faceted exploration of a complex phenomenon within its real-life context [8, 17]. S21 represents a "critical case" for understanding megaproject failure, as its well-documented history of planning, conflict, and cost escalation offers a rich and detailed dataset for examining the interplay of financial, technical, and political factors over time. The longitudinal design, which tracks developments over a period of approximately thirty years (from 1994 to 2024), is essential for capturing the evolution of decisions, the emergence of risks, and the long-term consequences of the initial project framework [8].

The research is based on a systematic review and synthesis of a wide range of publicly available documents and secondary sources. This desk-based approach was chosen due to the extensive public documentation surrounding the S21 project, a result of its high political profile and legal challenges. The data sources were systematically collected and categorized to ensure comprehensive coverage and to allow for triangulation of information. These sources fall into four main categories:

1. **Primary Project and Corporate Documents:** This category includes foundational documents that shaped the project's scope and governance. Key among these are the original 1996 feasibility study (Die Machbarkeitsstudie) [7], which established the project's initial concept and cost estimates, and the pivotal 2009 Financing Agreement (Finanzierungsvertrag) [9], signed by Deutsche Bahn (DB), the German federal government, the State of Baden-Württemberg, the regional authority (Verband Region Stuttgart), the state capital (Landeshauptstadt Stuttgart), and Stuttgart Airport. This document legally defined the project budget and cost-sharing arrangement. Other sources in this category include official risk analysis reports published by the project company [12], integrated annual reports from the parent company, Deutsche Bahn AG [5], and information from the official project website managed by DB Projekt Stuttgart–Ulm GmbH [4, 6, 29, 30].
2. **Governmental and Legal Documents:** To understand the political and legal context, this study draws on official government records and court filings. This includes the 2006 parliamentary resolution (Entschließung) from the Landtag of Baden-Württemberg, which documented political support for the project [20]. Critically, this research relies on the official press releases and summaries concerning the Stuttgart Administrative Court's landmark decision in May 2024 regarding the lawsuit over cost overruns [11].
3. **Peer-Reviewed Academic Literature:** A review of scholarly work provides the theoretical framework for the analysis. This includes seminal works on megaproject management, particularly the concepts of optimism bias and the "planning fallacy" [10], as well as research on project success criteria [33], risk management frameworks like the Risk Breakdown Structure [14], project readiness [24], stakeholder management [32], and critical failure factors [22]. General project management principles

from sources like Verzuh [31] and the concept of financial intelligence from Berman and Knight [2] also inform the analysis.

4. **Archival and Reputable Journalistic Sources:** Given the project's long and controversial history, high-quality journalistic reporting provides an invaluable chronological record of events, public discourse, and stakeholder positions. This study utilizes reports from major German news outlets such as Der Spiegel [3, 18], tagesschau.de [15], ZDFheute [16], WirtschaftsWoche [23], and the regional public broadcaster SWR Aktuell [28]. In addition, detailed chronologies compiled by watchdog organizations like ansTageslicht.de [27] and environmental groups like BUND [26] were used to reconstruct the timeline and understand specific points of contention.

The analytical strategy employed is a combination of chronological and thematic analysis. The chronological analysis involves constructing a detailed timeline of the S21 project, mapping key milestones (e.g., feasibility study, financing agreement, start of construction, court ruling) against the publicly announced cost estimates. This approach is essential for demonstrating the process of cost escalation over time. The thematic analysis involves identifying, coding, and categorizing key themes that emerge from the data. These themes are guided by the research questions and include "initial fiscal framework," "risk identification and mitigation," "drivers of cost escalation" (e.g., geological, political, regulatory), and "liability and governance disputes." By systematically analyzing the content of the financing agreement, risk reports, and court records, this study deconstructs the formal mechanisms of project governance and compares them to the practical outcomes documented in media and official reports. This dual approach allows for a narrative reconstruction of S21's history that is both temporally ordered and thematically rich, providing a robust foundation for the subsequent discussion and conclusions. A key limitation of this study is its reliance on publicly accessible data, which may reflect the inherent biases of the organizations that produced them. The study seeks to mitigate this by triangulating information from diverse sources (e.g., comparing project company reports with critical media coverage).

RESULTS

The longitudinal analysis of the Stuttgart 21 project reveals a clear and dramatic trajectory of fiscal decay and risk realization. The project's history can be divided into three distinct phases: a period of conception and contractual agreement marked by optimism; a long period of construction defined by escalating controversy and costs; and a final phase characterized by legal conflict over financial liability.

3.1 Phase 1: Project Genesis and the Optimistic Financing Agreement (1994–2009)

The origins of Stuttgart 21 date back to 1994, when the concept of transforming Stuttgart's main station was first formally proposed as part of a broader vision for improving European high-speed rail networks [30]. The initial feasibility study, presented by Deutsche Bahn in 1995, outlined the ambitious engineering plan and provided a preliminary cost estimate of 4.986 billion Deutsche Mark, equivalent to approximately €2.6 billion [7, 27]. This initial figure became the first of many cost benchmarks that would be

progressively abandoned over the project's life. For over a decade, the project moved through various stages of planning and political negotiation, with costs being periodically adjusted. By 2006, when the Landtag of Baden-Württemberg passed a resolution in support of the project, the estimated costs had already begun to climb, but political will remained strong [20].

The most critical event of this initial phase occurred on April 2, 2009, with the signing of the formal Financing Agreement (Finanzierungsvertrag) by all major project partners: Deutsche Bahn AG, the German federal government, the State of Baden-Württemberg, the regional authority (Verband Region Stuttgart), the state capital (Landeshauptstadt Stuttgart), and Stuttgart Airport [9]. This legally binding document was intended to provide long-term financial certainty for the project. It established a total budget of €4.526 billion. This figure was composed of €3.076 billion for the Stuttgart 21 station project and €1.45 billion for the associated Wendlingen-Ulm high-speed line section [9].

The agreement meticulously detailed the cost-sharing arrangement among the partners. Deutsche Bahn was to contribute €1.597 billion, the State of Baden-Württemberg agreed to €930 million, the City of Stuttgart provided €292 million, and the federal government committed to €1.117 billion, with smaller contributions from the airport and region [9]. Crucially, the contract included a clause (§8, Abs. 1) that became the central point of contention in later years. It stated that the partners were only obligated to their specified contributions and that any potential cost increases were to be discussed among the partners to find a solution. However, it did not explicitly pre-allocate liability for overruns beyond the €4.526 billion ceiling, an ambiguity that would prove catastrophic. At the time, the partners celebrated the agreement as a historic achievement that paved the way for construction, operating under the implicit and highly optimistic assumption that the established budget was robust and achievable.

3.2 Phase 2: Construction, Controversy, and Uncontrolled Cost Escalation (2010–2022)

The official start of construction on February 2, 2010, marked the beginning of S21's most turbulent phase. The project immediately faced fierce public opposition. Protests grew throughout 2010, fueled by concerns over the project's immense cost, the felling of old trees in the adjacent Schlossgarten park, and doubts about the operational benefits of the new station [18]. The conflict escalated dramatically in what became known as "Black Thursday" on September 30, 2010, when police used water cannons and pepper spray on demonstrators, further polarizing the public and entrenching opposition [18].

While political and social battles raged on the surface, a financial crisis was brewing underground. The complex tunnelling required for the project encountered geological conditions that were reportedly more challenging and expensive to manage than anticipated. Furthermore, updated regulations concerning safety, noise abatement, and environmental protection imposed additional requirements not fully accounted for in the 2009 budget. For instance, extensive measures were required for species protection, including the relocation of thousands of protected Juchtenkäfer (*Osmoderma eremita*) beetle larvae, a process that became symbolic of the project's unforeseen complexities and costs [26].

The financial framework established in 2009 soon proved to be wholly inadequate. The timeline of cost escalation, as documented by sources like SWR Aktuell, is stark [28]:

- December 2012: Deutsche Bahn officially acknowledged for the first time that the project would exceed its budget. The new cost estimate was presented in March 2013: €6.5 billion, an increase of nearly €2 billion. The reason given was a combination of higher-than-expected construction and planning costs [27, 28].
- January 2018: The project's supervisory board approved a new cost framework, raising the official estimate to €8.2 billion. This increase was attributed to a risk buffer for further geological and technical challenges, as well as rising prices in the construction sector [28].
- March 2022: Deutsche Bahn internally updated its cost projections again, this time to €9.15 billion [28].
- December 2023 / January 2024: In the lead-up to the legal proceedings, the figure continued to climb. A "worst-case" scenario including all potential risks put the total projected cost at 11.45 billion, more than 2.5 times the original financing agreement budget [15, 23].

Throughout this period, Deutsche Bahn maintained that these cost increases were the result of risks inherent to a project of this scale and that the other partners should share the financial burden. The project partners, however, steadfastly pointed to the 2009 agreement, arguing their liability was capped at their contractually specified contributions [3]. A 2011 internal risk assessment from a DB subsidiary had already identified potential for significant cost and schedule deviations, but these warnings failed to alter the project's public financial footing or governance structure at the time [12]. The company's overall financial health remained a topic of public interest, with reports on its net income showing the strain of such massive capital projects [5, 19].

3.3 Phase 3: The Legal Battle for Liability (2022–2024)

With costs spiralling far beyond the agreed-upon ceiling and with no amicable agreement in sight, Deutsche Bahn escalated the dispute to the courts. In late 2022, DB formally filed a lawsuit against its project partners—the State of Baden-Württemberg, the City of Stuttgart, the Verband Region Stuttgart, and Flughafen Stuttgart GmbH—at the Stuttgart Administrative Court [15]. The lawsuit sought to compel the partners to pay a share of the cost overruns, amounting to several billion euros. Deutsche Bahn's central argument was that the 2009 contract implied a shared responsibility for all project costs, and that as beneficiaries of the project, the partners had an obligation to contribute to the funds necessary for its completion. They argued it was untenable that a single partner should shoulder the entirety of unforeseen, but necessary, cost increases [23].

The project partners mounted a unified defence. Their argument was simple and rested on a strict interpretation of the 2009 Financing Agreement. They contended that the contract explicitly defined their financial contributions and contained no clause obligating them to further payments. They argued that they had fulfilled their contractual duty and that Deutsche Bahn, as the project developer and owner (Bauherr), bore the entrepreneurial risk, including the risk of cost overruns [15]. The trial, which began in May 2023, was closely watched across Germany as a landmark case in public project financing [23].

On May 7, 2024, the Stuttgart Administrative Court delivered its verdict. In a decisive ruling, the court dismissed Deutsche Bahn's lawsuit in its entirety [11, 16]. The judges concluded that the 2009 Financing Agreement was clear and unambiguous. It specified the exact financial contributions of the partners and did not contain any provision for a subsequent obligation to fund cost overruns. The court found no legal basis for DB's claim that the partners must share in the increased costs [11]. The verdict effectively placed the financial responsibility for all costs exceeding the partners' fixed contributions squarely on Deutsche Bahn. While DB announced its intention to appeal, the initial ruling represented a stunning legal and financial defeat for the company and a complete vindication for the project partners. It brought the project's long and troubled financial journey full circle, from an optimistically framed contract to a definitive legal judgment that exposed the profound flaws in its foundational premise.

DISCUSSION

The results of the longitudinal analysis of Stuttgart 21 provide a rich and sobering account of megaproject failure, offering profound lessons that resonate far beyond this single case. The project's trajectory from a celebrated vision to a multi-billion-euro financial quagmire can be interpreted through the lenses of established megaproject theory, while also offering new insights into the critical importance of adaptive governance and fiscal realism. The discussion will first interpret the findings in relation to the academic literature, then explore the theoretical and practical implications of the case, and finally acknowledge the study's limitations.

4.1 Interpretation of Findings: A Case Study in the Planning Fallacy

The history of Stuttgart 21 is a near-perfect illustration of the concepts of "optimism bias" and the "planning fallacy" as described by Flyvbjerg [10] and others [22]. The initial cost estimate of €4.526 billion codified in the 2009 Financing Agreement [9] was not, in retrospect, a realistic forecast derived from a rigorous and pessimistic risk analysis. Instead, it functioned as a political and financial instrument designed to make the project palatable to stakeholders and secure the necessary approvals to move forward. The very structure of the agreement, which precisely capped the partners' contributions but left the allocation of potential overruns dangerously ambiguous, suggests a collective institutional desire to believe the project could be delivered within this optimistic budget. This willful optimism ignored the immense uncertainties inherent in a project involving a decade or more of complex tunnelling under a major city.

The subsequent and repeated cost escalations were not random events but the predictable realization of risks that were either systematically underestimated or ignored in the initial planning phase. The 2011 internal DB risk report [12], which warned of potential overruns, confirms that an awareness of the financial danger existed within the organization shortly after construction began, yet the project's external governance structure remained tied to the obsolete 2009 agreement. This demonstrates a critical failure in project readiness [24] and financial intelligence [2]; the stakeholders lacked the frameworks and perhaps the will to confront the project's true financial risk profile early on. The litany of reasons cited for the cost increases—challenging geology, new regulations, environmental protection [26], and rising construction prices—are precisely the types of emergent risks that robust megaproject management is supposed to anticipate and mitigate [14, 31]. In the S21 case, the static financial model was brittle, unable to absorb and manage these pressures, causing it to shatter rather than adapt.

The final legal verdict [11, 16] serves as a powerful epilogue to this failure. The court's strict, literal interpretation of the financing contract [9] highlights a fundamental flaw in the project's governance. The partners entered into a rigid, transactional agreement for a project that required a dynamic, relational approach [32]. The lack of a pre-agreed, flexible mechanism for allocating and funding overruns transformed what should have been a collaborative problem-solving process into an adversarial, zero-sum legal conflict. The court did not rule on what would have been fair or prudent, but simply on what the contract stipulated. This outcome reveals that the initial agreement was not a tool for effective project delivery but a fragile truce built on an unsustainable financial premise. The failure was not merely one of cost estimation; it was a profound failure of governance design.

4.2 Theoretical and Practical Implications

The Stuttgart 21 case has significant implications for both megaproject theory and practice. Theoretically, it reinforces the argument that traditional project management frameworks, focused on the "iron triangle" of scope, time, and cost, are insufficient for managing megaprojects [25]. The success or failure of these ventures is determined less by adherence to a static baseline plan and more by the adaptive capacity of their governance systems. The S21 case suggests that megaproject success criteria [33] must be expanded to include measures of institutional resilience and the robustness of financing and risk-sharing mechanisms over the long term. It powerfully demonstrates that relational quality among stakeholders [32] cannot be assumed; it must be explicitly engineered into the governance framework through clear, enforceable, and adaptive contractual clauses.

Furthermore, the case challenges the efficacy of fixed-cost-sharing models for public-private partnerships in projects with high uncertainty. The S21 financing agreement [9] privatized the risk of overruns by default onto a single partner (DB), creating perverse incentives and fostering conflict rather than collaboration. This suggests that theoretical models of megaproject finance need to more strongly advocate for dynamic funding models that incorporate structured contingency funds, clear triggers for their release, and pre-agreed formulas for handling overruns that exceed contingency levels.

From a practical standpoint, the lessons from S21 are stark and actionable for policymakers, project sponsors, and managers worldwide:

1. **Mandate Independent, Pessimistic Forecasting:** Project approval should never be based on cost estimates produced solely by the project's proponents. Governments and investors must mandate independent, third-party reviews of cost, schedule, and risk, employing techniques like "reference class forecasting" [10] to ground estimates in the actual outcomes of comparable past projects. This fosters a culture of fiscal prudence from the outset [2].
2. **Design Adaptive Contracts for an Uncertain World:** For long-term projects, static contracts are a recipe for disaster. Financing and partnership agreements must be designed as adaptive instruments. This includes establishing large, transparent contingency funds controlled by an independent body, and, critically, defining clear contractual mechanisms for allocating costs that exceed even those contingencies. Instead of leaving overruns to future negotiation, contracts should pre-specify the process and formulas for managing them.
3. **Integrate Risk Management with Governance:** Risk management cannot be a siloed technical exercise [14]; it must be deeply integrated into the project's governance structure. The S21 case shows that identifying a risk [12] is meaningless if the governance framework provides no mechanism to act on that information. Governance bodies must have the authority and the contractual tools to adjust budgets, re-scope work, or even halt a project in response to realized risks.
4. **Prioritize Transparent Stakeholder Management:** The intense public opposition to S21 [18] was a significant, and costly, risk factor. While not the direct cause of all cost overruns, the resulting political friction and project modifications contributed to the difficult environment. Megaproject success depends on securing and maintaining a social license to operate, which requires transparent communication and genuine engagement with all stakeholders, including the public and environmental groups [26], from the earliest stages.

4.3 Limitations and Avenues for Future Research

This study is subject to certain limitations. Its reliance on publicly available documents means it is susceptible to the potential biases within those sources, whether it is the self-promoting language of corporate reports [5] or the critical framing of journalistic coverage. It lacks the insider perspective that could be gained from interviews with the key decision-makers involved. Nonetheless, the triangulation of data from legal, corporate, government, and media sources provides a high degree of confidence in the reconstructed narrative.

The Stuttgart 21 saga opens up several avenues for future research. Now that the primary court verdict is in, a comparative legal analysis of how other countries' legal systems handle similar disputes over public project overruns could yield valuable insights. Furthermore, as the project nears its (delayed) completion,

a post-completion audit will be essential. Such a study should analyze whether the project's originally promised benefits—in terms of travel time savings, urban development, and economic growth—materialize, and how those benefits weigh against its final, monumental cost. This would provide a complete, cradle-to-grave analysis of S21's ultimate value proposition and serve as an even more powerful lesson for the next generation of megaprojects.

CONCLUSION

The Stuttgart 21 project, conceived as a visionary leap forward in European infrastructure, ultimately serves as a powerful and cautionary tale of fiscal and managerial failure. This longitudinal analysis has demonstrated that the project's journey from a celebrated ambition to a symbol of financial mismanagement was not accidental but was systematically rooted in its foundational framework. The core findings indicate that a combination of profound optimism bias in initial planning, a rigid and inadequate financing contract incapable of handling emergent risks, and a failure of governance to adapt to reality drove the project into a multi-billion-euro crisis. The predictable realization of technical, political, and environmental risks, coupled with an inflexible cost-sharing model, culminated in an adversarial legal battle that exposed the unsustainability of the original agreement.

The primary contribution of this paper is its comprehensive, start-to-finish analysis that connects the dots between flawed initial assumptions and the project's ultimate legal and financial consequences. It moves beyond simply listing failure factors to illustrate the process of failure as it unfolds over decades.

The final verdict on Stuttgart 21's cost overruns delivers a clear and unequivocal message for the future of megaprojects globally: risk and financial liability must be allocated with transparency, realism, and adaptability from the very outset. Initial agreements built on hope rather than rigorous, pessimistic analysis will inevitably crumble under the immense pressures of megaproject reality, leaving a legacy of financial burden and public mistrust. The lessons from Stuttgart 21 are not merely academic; they are an essential guide for preventing the next great infrastructure catastrophe.

REFERENCES

Ashkanani, S., & Franzoi, R. (2022). An overview on megaproject management systems. *Management Matters*, 19(2), 129-148. <https://doi.org/10.1108/MANM-01-2022-0006>

Berman, K., & Knight, J. (2013). *Financial intelligence*. Harvard Business Review Press.

Böll, S. (2011, April 11). Grün-rot und stuttgart 21: Viel Geld, wenig Bahnhof. *Der Spiegel*. <https://www.spiegel.de/wirtschaft/unternehmen/gruen-rot-und-stuttgart-21-viel-geld-wenig-bahnhof-a-759527.html>

DB Projekt Stuttgart–Ulm. (n.d.). Stuttgart 21-Überblick. Retrieved August 6, 2025, from <https://www.bahnprojekt-stuttgart-ulm.de/projekt/ueberblick/stuttgart-21/>

Deutsche Bahn AG. (2022). Deutsche Bahn 2022 integrated report.

Deutsche Bahn. (n.d.). Architektur. Retrieved August 6, 2025, from <https://www.bahnprojekt-stuttgart-ulm.de/projekt/stuttgart-filder-s21/neue-bahnhoefe/hauptbahnhof-stuttgart/architektur/>

Deutsche Bahn AG. (1996). Die Machbarkeitsstudie | Projekt "Stuttgart 21".

Eduardo Yamasaki Sato, C., & De Freitas Chagas Jr, M. (2014). When do megaprojects start and finish? Redefining project lead time for megaproject success. International Journal of Managing Projects in Business, 7(4), 624-637. <https://doi.org/10.1108/IJMPB-07-2012-0040>

DB Netz AG, Land Baden-Württemberg, Landeshauptstadt Stuttgart, Verband Region Stuttgart, & Flughafen Stuttgart GmbH. (2009). Finanzierungsvertrag.

Flyvbjerg, B. (2017). Megaprojects: Over budget, over time, over and over. Cato Institute Policy Report. <https://www.cato.org/policy-report/january/february-2017/megaprojects-over-budget-over-time-over-over>

Baden-Württemberg.de. (2024, May 7). Gerichtsentscheidung über S-21-Mehrkostenklage der Bahn. Retrieved August 6, 2025, from <https://www.baden-wuerttemberg.de/de/service/presse/pressemitteilung/pid/verwaltungsgerichtsentscheidung-zur-stuttgart-21-klage>

DB Projekt Bau GmbH. (2011). Großprojekt Stuttgart 21-Wendlingen-Ulm Chancen und Risiken.

He, Q., Xu, J., Wang, T., & Chan, A. P. C. (2021). Identifying the driving factors of successful megaproject construction management: Findings from three Chinese cases. Frontiers of Engineering Management, 8(1), 5-16. <https://doi.org/10.1007/s42524-019-0058-8>

Hillson, D. (2003). Using a risk breakdown structure in project management. Journal of Facilities Management, 2(1), 85-97. <https://doi.org/10.1108/14725960410808131>

Hörger, D. (2023, May 8). Verwaltungsgericht verhandelt über Klage der Bahn zu "Stuttgart 21"-kosten. tagesschau.de. <https://www.tagesschau.de/wirtschaft/finanzen/kosten-stuttgart-21-verhandlung-100.html>

Houben, L. (2024, May 7). Stuttgart 21: Bahn muss Mehrkosten zahlen. ZDFheute. <https://www.zdf.de/nachrichten/politik/deutschland/stuttgart-21-mehrkosten-urteil-deutsche-bahn-100.html>

Hu, Y., Chan, A. P. C., & Le, Y. (2015). Understanding the determinants of program organization for construction megaproject success: Case study of the Shanghai Expo construction. Journal of Management in Engineering, 31(5), 05014019. [https://doi.org/10.1061/\(ASCE\)ME.1943-5479.0000310](https://doi.org/10.1061/(ASCE)ME.1943-5479.0000310)

Published Date: - 01-09-2025

E-ISSN: 2536-7897

P-ISSN: 2536-7889

SJIF 2019: 4.486 2020: 4.669 2021: 5.037

Kaiser, S., & Windmann, A. (2010, October 1). The "Stuttgart 21" revolt: Protests against mega project grow. Der Spiegel. <https://www.spiegel.de/international/germany/the-stuttgart-21-revolt-protests-against-megaproject-grow-a-713375.html>